



59 Route 125
Kingston, New Hampshire 03848
Tel: 603-642-6677 Fax: 603-642-6658

Granite Step Installation Checklist:

The following requirements must be met before Landscapers Depot can perform any granite step installations at your home or job site. Please read and check off each item below to acknowledge that you have met our requirements.

*****Failure to meet these requirements could result in inability to install ***
your steps, and additional charges for lost time.**

- Area must be clear of fencing, retaining walls, rocks, shrubbery etc within a 10' radius of the work area in order for the fork lift to maneuver.
- Check here ONLY if your steps are to be installed in an alcove. An alcove is any area where the steps are up against more then 1 side of your house. The steps for this type of installation may require modification which may add additional costs, consult an associate for more details.
- All siding or wood paneling must be removed from the area where the steps are being installed as well as an additional 6" past the width of the stairs. Landscapers Depot crews are not authorized to remove any siding or paneling from your home or building.

CEMENT PAD: A minimum 4" thick concrete pad must be poured to the following specifications on ALL Landscapers Depot Granite Step Installs:

- Pad must be no shorter then the width of the steps being installed.
Ex: For 6' wide stairs, the pad must be 72" wide or larger.
- Pad must be no shorter then 3" of the total depth of the staircase footprint. This is so that any bricks or pavers leading up to the steps may be tucked under the steps. Use the following formula to calculate this dimension:
*Depth of landing (in feet) ___' + # of steps (excluding landing) ___ = ___' Depth of staircase
Subtract 3" from that figure ___" and this is the ideal depth of your concrete pad.*
- Pad must be level from left to right, and must have a 1/4" pitch away from the house (back to front) for proper water drainage.
- Surface must be screeded and troweled ALL THE WAY to the foundation, and must be free from bumps and irregularities.
- From the top of the concrete pad to the bottom of the threshold must be divisible by 7" (+/- 1/2")

I understand that Granite is a natural product and is prone to natural variations in color which could include veining and marbling. _____ **Customer Initials**

By signing below I acknowledge that I have read all the above requirements and have met them. If the installation crew is unable to complete the install due to unmet requirements a fee of \$100/per hour (including travel time) will be charged.

X _____ Date _____